

ANNEXURE CQS-C
MAXIMUM LOT SIZES AND MINIMUM TEST FREQUENCIES

GENERAL

1. The maximum lot sizes and minimum test frequencies are separately specified for all major activities covered by the Technical Specifications as listed hereunder.
2. The requirements applicable to this Contract are identified with an asterisk indicating that only these details are attached in this Annexure.
3. Where material/product quality certification can be obtained from the supplier, tests listed per contract/separable part need not be repeated.

Contents of Annexure CQS-C

Item	Sub-Annexure	Required (*) for this Contract	Reference Specification	Sub-Annexure Heading
1	C1		C213	Earthworks
2	C2		C220 C221 C222 C223 C224	Stormwater Drainage - Pipe Culverts, Box Culverts, Open Drains, Kerb & Gutter, Drainage Structures
3	C3		C230 C231 C232 C233	Subsurface Drainage
4	C4		C241	Stabilisation
5	C5		C242	Flexible Pavements
6	C6		C244	Sprayed Bituminous Surfacing
7	C7		C245	Asphaltic Concrete
8	C8		C247 C248	Ready Mixed Concrete Production and Supply
9	C9		C247	Mass Concrete Subbase
10	C10		C248	Plain or Reinforced Concrete Base
11	C11		C255	Bituminous Microsurfacing
12	C12		C254	Segmental Paving
13	C13		C271	Minor Concrete Works
14	C14		C261	Pavement Markings
15	C15		C262	Signposting
16	C16		C273	Landscaping
17	C17		C401	Water Reticulation
18	C18		C402	Sewerage System

Sub-Annexure B1
EARTHWORKS (Specification C213)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Stripping Topsoil	Surface Levels	10,000m ²	1 Cross Section per 25m	Survey
Excavation	Geometry	10,000m ²	1 Cross Section per 25m	Survey
Floor of Cuttings	Material Quality - CBR	5,000m ²	1 per 1,000m ² *	AS1289.6.1.1
	Compaction	10,000m ²	1 per 500m ²	AS1289.5.4.1
Foundation for Embankments	Compaction	5,000m ²	1 per 500m ²	AS1289.5.4.1
Embankments - General Road Carriageway Embankments - Select Zone	Geometry	One layer 10,000m ²	1 Cross Section per 25m	Survey
	Material Quality - CBR	One layer 5,000m ²	1 per 800m ³	AS1289.6.1.1
	Compaction/Moisture Content	One layer 5,000m ²	1 per 1000m ²	AS1289.5.1.1 AS1289.5.4.1 AS1289.5.7.1
	Geometry	One layer 10,000m ²	1 Cross Section per 25m	Survey
	Material Quality - Maximum Particle Size - CBR	10,000m ² 10,000m ²	1 per 1,000m ³ * 1 per 500m ³ *	AS1289.6.1.1
	Compaction/Moisture Content	One layer 5,000m ²	1 per 1000m ²	AS1289.5.1.1, AS1289.5.4.1 AS1289.5.7.1
Fill Adjacent to Structures: Bridges, Retaining Walls and Cast-in-Situ Culverts	Material Quality			
	- Maximum Particle Size - Plasticity Index	1 Structure 1 Structure	1 per 200m ³ * 1 per 200m ³ *	AS1289.3.3.1
	Compaction/Moisture Content	1 Structure	1 per layer	AS1289.5.1.1, AS1289.5.4.1 AS1289.5.7.1

* Note: or part thereof, per lot.

Sub-Annexure B2

**STORMWATER DRAINAGE - PIPE CULVERTS, BOX CULVERTS, OPEN DRAINS
INCLUDING KERB & GUTTER, DRAINAGE STRUCTURES
(Specifications C220, C221, C222, C223, C224)**

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Supply of Precast Units	Precast Quality - Suppliers documentary evidence and certification	1 batch	1 per type/size/ class per batch	
Siting and Excavation	Geometry	1 drainage line/structure	1 per drainage line/structure	Survey
Foundation	Compaction	1 drainage line/structure	1 per 20 lin m *	AS1289.5.4.1
Material surrounding Steel Structures	Material Quality - pH/Electrical Resistivity	1 drainage line/structure	1 per material	AS1289.4.3.1 AS1289.4.4.1
Bedding	Material Quality - Particle Size Distribution Compaction/Moisture Content	1 contract 1 drainage line/structure	1 per 200m ³ * 1 per layer, per 20 lin m	AS1141.11 AS1289.5.7.1, AS1289.5.4.1
Concrete Bedding or Lining	Geometry		1 Cross Section per 25m	Survey and 3m Straight Edge
Installation of Precast Units	Geometry	1 drainage line/structure	1 per drainage line/structure	Survey
Embedment material for drainage lines under roads or kerbs, other than "Bedding	Material Quality - Particle Size Distribution Compaction/Moisture Content	1 contract 1 drainage line/structure	1 per 200m ³ * 1 per 2 layers per 50m ² (Full 300mm test depth)	AS1141.11 AS1289.5.7.1, AS1289.5.4.1
Selected Backfill	Material Quality - Maximum Particle Size - Plasticity Index Compaction/Moisture Content	1 contract 1 contract 1 drainage line/structure	1 per 100m ³ * 1 per 100m ³ * 1 per 2 layers per 50m ²	AS1289.3.3.1 AS1289.5.7.1, AS1289.5.4.1
Rock Fill for Gabions/ Wire Mattresses	Material Quality: - Wet Strength - Wet/Dry Strength Variation	1 contract 1 contract	1 per contract 1 per contract	AS1141.22 AS1141.22
Kerb and Gutter	Geometry		1 Cross Section per 25m	Survey and 3m Straight Edge

* Note: or part thereof, per lot.

Sub-Annexure B3

SUBSURFACE DRAINAGE (Specifications C230, C231, C232, C233)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Material Supply	Material Quality - Supplier's documentary evidence and certification of: Pipe Filter Material - Grading (Type A, B, C, D) - Coefficient of Permeability (Type B) - Grading Variation after Treatment (Type B) - Wet Strength (Type C, D) - 10% Fines Wet/Dry (Type C, D) Geotextile	1 contract/size 1 contract/size 1 contract/size 1 contract/size 1 contract/size 1 contract/size 1 contract	1 per type/size 1 per type 1 per type 1 per type 1 per type 1 per type	AS1141.11 AS1289.E5.1 ASTM-D2434-68 AS1141.11 AS1141.22 AS1141.22
Excavation - Trench Base	Line and Grade Compaction	1 drainage line 1 drainage line	1 per drainage line 1 per 200 lin m*	Survey AS1289.5.4.1
Bedding and Backfill				
- Filter Material	Compaction	1 drainage line	1 per drainage line	AS1289.5.4.1
- Selected Backfill	Compaction	1 drainage line	1 per 200 lin m*	AS1289.5.4.1
- Earth Backfill	Compaction	1 drainage line	1 per 200 lin m*	AS1289.5.4.1
Drainage Mat	Geometry	2000m ²	1 Cross Section per 25m	Survey

* Note: or part thereof, per lot

Sub-Annexure B4
STABILISATION (Specification C241)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Material Supply	Material Quality - Supplier's documentary evidence and certification of: - Cement - Quicklime · Available Lime (CaO content) · Slaking Rate · Particle Size Dist'n - Hydrated Lime · Available Lime (CaOH₂) · Residue on Sieving - Ground Blast Furnace Slag - Flyash - Blended Stabilising Agent - Water - Chloride ion content - Sulphate ion content - Undissolved solids	1 contract 1 contract 1 contract 1 contract 1 contract 1 contract 1 contract 1 contract 1 contract 1 contract 1 contract	1 per 100t 1 per 100t 1 per 100t 1 per contract 1 per 100t 1 per contract 1 per month 1 per month 1 per month 1 per contract 1 per contract 1 per contract	AS3972 AS3583.12 T432 AS1141.11 AS3583.12 AS3583.14 AS3583.2 AS3583.1 AS3583.13 AS1289.4.2.1
Mix Design	NATA certification - Supplier's documentary evidence and certification	1 mix	1 per mix	
Stationary Mixing Plant	Application rate of stabilising agent Compressive strength of product	1 day's production 1 day's production	1 per 100t 1 per 400t	AS1289.6.1.1
In-Situ Spreading	Spread rate	1 layer 1,000m ²	1 per lot or 1 per 500m ²	
Trimming and Compaction	Geometry Surface Quality Average Layer thickness Average Width Relative Compaction/Moisture Content	1 layer 2,000m², max 1 day's placement " " " "	One cross section per 25m 10 per 200m lane length * 1 per lot 1 per lot 3 per lot	Survey 3m Straight Edge Measure/Survey AS1289.5.7.1 AS1289.5.8.1

* Note: or part thereof, per lot.

Sub-Annexure B5

FLEXIBLE PAVEMENTS (Specification C242)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Base and Subbase Supply	Material Quality - Supplier's documentary evidence and certification	1 contract		
	- Particle Size Distribution		1 per 1,000t	AS1289.3.6.1
	- Fine Particle Size Distribution Ratio		1 per 1,000t	AS1289.3.6.3
	- Liquid Limit		1 per 1,000t	AS1289.3.1.1
	- Plastic Limit		1 per 1,000t	AS1289.3.3.1
	- Plasticity Index		1 per 1,000t	AS1289.3.3.1
	- Maximum Dry Compressive Strength		1 per 5,000t	T114
	- Particle Shape		1 per 1,000t	AS1141.14
	- Aggregate Wet Strength		1 per 5,000t	AS1141.22
	- Wet/Dry Strength Variation		1 per 5,000t	AS1141.22
	- Modified Texas Triaxial Classification		1 per contract	T171
	- Unconfined Compressive Strength (Modified)		1 per 5,000t	T116
	- Unconfined Compressive Strength (Bound)	1 contract	1 per mix design	T131
Placement	Geometry: Alignment & Level	One layer 2,000m ² or max 1 day's placement	1 Cross Section per 15m	Survey
	Width & Surface Trim		10 per selected 200 lin m*	Measure & 3m Straight Edge
	Deflection Control - Benkelman Beam	One layer 5,000m ² or max 1 day's placement	4 per 1,000m ² minimum 10 per lot	T160
	Compaction/Moisture Content/ Dry Density Testing	One layer 5,000m ² or max 1 day's placement	10 per 5,000m ² layer or 3 per lot if less	AS1289.5.2.1, T130, AS1289.5.4.1 AS1289.5.8.1

* Note: or part thereof, per lot.

Sub-Annexure B6

SPRAYED BITUMINOUS SURFACING (Specification C244)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Materials Supply	Material Quality - Suppliers documentary evidence and certification of: - Class 170 Bitumen - Refinery Cutback Bitumen - Polymer Modified Binder - Bitumen Adhesion Agent - Cutback Oils - Aggregate Precoating Agent - Aggregate	1 tanker load 1 tanker load 1 tanker load 1 delivery 1 delivery/ tanker 1 delivery/ tanker 1 contract	1 per tanker load 1 per tanker load 1 per tanker load 1 per delivery 1 per delivery/tanker 1 per delivery/tanker 1 per 400m3	AS2758.2
Application Rates	Binder Aggregate	1 day's operation 1 day's operation	Calculate per spray run Calculate per spray run	

† One per Contract or change in material

* Note: or part thereof, per lot

Sub-Annexure B7

ASPHALTIC CONCRETE (Specification C245)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Materials Supply	Material Quality - Supplier's documentary evidence and certification of: - Coarse & Fine Aggregates · Grading · Moisture Content · Wet Strength · Wet/Dry Strength Variation · Particle Shape · Fractured Faces · Polishing Agg Friction Value - Mineral Filler - Bitumen Binder - Polymer Modified Bitumen · Elasticity Recovery at 60°C · Viscosity on ER at 60°C · Torsional Recovery at 25°C · Viscosity at 180°C - Bitumen Adhesion Agent · Resistance to Stripping - Reclaimed Asphalt Pavement (RAP) - Bitumen Emulsion	1 wk's prod'n 1 wk's prod'n 1 contract 1 contract 1 contract 1 contract 1 contract 1 contract or 1 month's production 1 refinery batching 1 production batch by supplier 1 contract 1 stockpile 1 contract	1 per day 1 per day)) 1 per) contract) or change in) material - contract or 1 per month's production 1 per tanker load 1 per tanker load 1 per contract or change in material 1 per stockpile 1 per contract or change in material	- AS2758.5 - AS1141.11 - AS1289.2.1.1 - AS1141.22 - AS1141.22 - AS1141.14 - AS1141.18 - AS1141.42 - AS2357 - AS2008 - MBT 21 - MBT 21 - MBT 22 - MBT 11 - T230 or nominated equivalent - AS1141.11 - AS1160
Mix Design - Nominated Mix	Approval of mix and NATA certification. Supplier's documentary evidence and certification	1 mix per contract	1 per mix	
Production Mix	Temperature Moisture Content Grading Binder Content	C245.7 from Spec C245 Asphaltic Concrete as included as separate table below. Additionally, max lot size one 12 hr shift's production.	1 per truck load	Measure AS2891.10 AS2891.3.3 AS2891.3.1
	Resistance to Stripping	1 production mix	1 per mix per 5000t or once per month (whichever is the most frequent)	T640

QUALITY SYSTEM REQUIREMENTS

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Laying and Compaction	Temperature	1 day's laying per site	1 per truck load	Measure
	Levels	1 day's laying per site	1 cross section per 25m	Survey
	Shape	1 day's laying	10 per 200m* lane length	3m Straight Edge
	Relative Compaction/Layer Thickness	1 day's laying	6 cores per lot 10 nuclear density tests per lot	AS2891.9.3 or Nuclear Density Meter

* Note: or part thereof, per lot

Quantity of Asphalt in production lot	Minimum Frequency of Testing
Less than 100 tonnes	One per 50 tonnes or part thereof
101 to 300 tonnes	One per 100 tonnes or part thereof
301 to 600 tonnes	One per 150 tonnes or part thereof
Over 600 tonnes	One per 200 tonnes or part thereof

Table C245.7 Minimum Testing Frequencies for Asphalt Production

Sub-Annexure B8

READY-MIXED CONCRETE PRODUCTION & SUPPLY

(Specifications C247, C248)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Raw Materials Supply	Material Quality - Supplier's documentary evidence and certification of:-			
	Cement	1 mth's prod'n	1 per week	AS 3972
	Flyash	1 mth's prod'n	1 per month	AS 3582.1
	Water	1 contract	1 per contract	AS3583.13, AS1289.4.2.1
	Admixtures	1 mth's prod'n	1 per month	AS 1478
	Fine Aggregates (C248 only)			
	- Grading	1 wk's prod'n	1 per 200m ³ concrete*	AS1141.11
	- Moisture Content	N/A	1 per day	
	- Sulphate Soundness	1 contract	1 per contract	AS1141.24
	- Bulk Density	1 contract	1 per contract	AS 2758.1
	- Unit Mass (particle density)	1 contract	1 per contract	AS 2758.1
	- Water Absorption	1 contract	1 per contract	AS 2758.1
	- Material Finer 2µm	1 contract	1 per contract	AS 2758.1
	- Deleterious Material (Impurities/Reactive)	1 contract	1 per contract	AS 2758.1
	- Combined Aggregates (C247 and C248)			
	- Grading	1 wk's prod'n	1 per 200m ³ concrete*	AS1141.11
	- Moisture Content	1 wk's prod'n	1 per day	
	- Wet Strength	1 contract	1 per contract	AS1141.22
	- Wet/Dry Strength Variations	1 contract	1 per contract	AS1141.22
	- Sulphate Soundness	1 contract	1 per contract	AS1141.24
	- Particle Shape	1 contract	1 per contract	AS1141.14
	- Fractured Faces	1 contract	1 per contract	AS1141.18
	- Bulk Density	1 contract	1 per contract	AS 2758.1
	- Unit Mass (particle density)	1 contract	1 per contract	AS 2758.1
	- Water Absorption	1 contract	1 per contract	AS 2758.1
	- Material Finer 75µm	1 contract	1 per contract	AS 2758.1

QUALITY SYSTEM REQUIREMENTS

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Raw Materials Supply (Cont'd)	- Weak Particles	1 contract	1 per contract	AS 2758.1
	- Light Particles	1 contract	1 per contract	AS 2758.1
	- Deleterious Materials (Impurities/Reactive)	1 contract	1 per contract	AS 2758.1
	- Iron Unsoundness	1 contract	1 per contract	AS 2758.1
	- Falling/Dusting Unsoundness	1 contract	1 per contract	AS 2758.1
Mix Design	Compressive Strength	1 contract mix	1 per mix per contract	AS1012.9
	Aggregate Moisture Content	1 contract mix	1 per mix per contract	
	Consistency - Slump	1 contract mix	1 per mix per contract	AS1012.3.1
	Air Content	1 contract mix	1 per mix per contract	AS1012.4 Method 2
	Shrinkage	1 contract mix	1 per mix per contract	AS1012.13

* Note: or part thereof, per lot

Sub-Annexure B9

MASS CONCRETE SUBBASE (Specification C247)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Concrete Supply	Refer Sub-Annexure B8: Ready-Mixed Concrete Production and Supply			
	Concrete/Air Temperature	50m ³	1 per 50m ³	Measure
	Air Content	50m ³	1 per 50m ³	AS1012.4 Method 2
	Consistency - Slump	50m ³	1 per load	AS1012.3.1
	Compressive Strength (7 day)	50m ³	1 pair per 50m ³	AS1012.1 AS1012.8 AS1012.9
	Compressive Strength (28 day)	50m ³	1 pair per 50m ³	AS1012.1 AS1012.8 AS1012.9
Placement	Thickness	50m ³	5m grid on plan area	Survey and check with subgrade survey
	Geometry	50m ³	1 cross section per 15m	Survey and 3m Straight Edge
Curing	Material Quality - Supplier's documentary evidence and certification	1 contract	1 per production batch	AS3799 AS1160
	Application Rate	1 day's work	1 per 1000m ² *	
Joints	Geometry	50m ³	All joints	Survey

* Note: or part thereof, per lot

Sub-Annexure B10

PLAIN OR REINFORCED CONCRETE BASE (Specification C248)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Concrete Supply	Refer Sub-Annexure B8: Ready-Mixed Concrete Production and Supply			
	Concrete/Air Temperature	50m ³	1 per 50m ³	Measure
	Air Content	50m ³	1 per 50m ³	AS1012.4 Method 2
	Consistency - Slump	50m ³	1 per load	AS1012.3.1
	Compressive Strength (7 day)	50m ³	1 pair per 50m ³	AS1012.1 AS1012.8 AS1012.9
	Compressive Strength (28 day)	50m ³	1 pair per 50m ³	AS1012.1 AS1012.8 AS1012.9
Placement	Relative Compaction			
	- Machine Placed	50m ³	1 per 50m ³ *	AS1012.14
	- Hand Placed	Area between 2 consecutive const. joints or 50m ³ (whichever is the lesser)	2 per lot	AS1012.14
	Thickness	50m ³	5m grid on plan area	Survey
	Geometry	50m ³	1 cross section per 15m	Survey and 3m Straight Edge
Ride Quality	Profile Factor	1000m ²	10/lane/lot	3m Straight Edge
Surface Texture	Texture Depth	1000m ²	2 per lot	
Curing	Material Quality - Supplier's documentary evidence and certification	1 contract	1 per production batch	AS3799 AS1160
	Application Rate	1 day's work	1 per 1000m ² *	
Joints	Sealant Material Quality Supplier's documentary evidence and certification	1 contract	1 per prod'n batch	
	Geometry	50m ³	All joints	Survey

* Note: or part thereof, per lot

Sub-Annexure B11

BITUMINOUS MICROSURFACING (Specification C255)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Materials Supply	Material Quality - Supplier's documentary evidence and certification of:			
	- Bitumen (prior to emulsification)	1 contract	1 per contract or change in material	AS2008
	- Bitumen Emulsion			
	· Residual Binder Content (Residue from Evaporation)	1 contract	2 per bulk delivery	AS1160, App.D
	- Mineral Aggregates			
	· Degradation Factor	1 contract	1 per contract or 6 month period	AS1141.25
	· Los Angeles Value	1 contract	“	AS1141.23
	· Aggregate Wet Strength	1 contract	“	AS1141.22
	· Wet/Dry Strength Variation	1 contract	“	AS1141.22
	· Polished Aggregate Friction Value	1 contract	“	AS1141.42
	· Sand Equivalent	1 contract	“	AS1289.3.7.1
	- Mineral Filler	1 month's prod'n	“	AS2357
	- Combined Aggregate Grading	1 contract	“	AS1141.11, AS1141.12
Mix Design - Nominated Mix	Approval of mix and NATA certification - Supplier's documentary evidence and certification	1 contract	1 per mix	
Production Mix	Grading	1 day's prod'n or 50m ³ (whichever is the lesser)	2 per 50m ³ *	AS2891.3.1
	Residual Binder Content		2 per 50m ³ *	AS2891.3.1
Laying	Levels	1 layer, max 200m ³	1 cross section per 15m	Survey
	Surface Quality	1 layer, max 200m ³	10 per 100m* lane length	3m Straight Edge

* Note: or part thereof, per lot

Sub-Annexure B12
SEGMENTAL PAVING (Specification C254)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Materials Supply	Material Quality - Supplier's documentary evidence and certification of: - Concrete Segmental Paving Units - Clay Segmental Paving Units - Bedding Sand · Grading - Joint Filling Sand · Grading	1 contract 1 contract 1 contract 1 contract	1 per contract 1 per contract 1 per contract or change in material 1 per contract or change in material	AS1141.11 AS1141.11
Base	Geometry Surface Quality	One layer 5000m ² , max 1 day's placement "	One cross section per 25m 10 per 200m ² or lot	Survey 3m Straight Edge
Edge Restraints	Refer 'Minor Concrete Works'	1 day's placement	1 per 10 lin m	Measure/Survey
Laying Paver Units	Joint Width Geometry Surface Quality	1 day's placement 1 day's placement 1 day's placement	All joints One cross section per 15m 10 per 200m ² or lot	Measure Survey 3m Straight Edge

* Note: or part thereof, per lot

Sub-Annexure B13

MINOR CONCRETE WORKS (Specification C271)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Subgrade	Compaction	1000 lin m or 1000m ²	1 per 200 lin m or 200m ²	AS1289.5.4.1
Gravel Subbase Construction	Compaction	1 day's placement	1 per 100 lin m or 100m ²	AS1289.5.4.1
	Subbase Geometry	1 day's placement	1 per 25 lin m	3m Straight Edge
Steel Supply	Material Quality - Suppliers documentary evidence and certification	1 delivery	1 per production batch	
Ready-Mixed Concrete Supply	Material Quality - Suppliers documentary evidence and certification	1 contract	1 per mix type	
	Consistency - Slump	15m ³	1 per load	AS1012.3 Method 1
	Compressive Strength (7 and 28 day)	15m ³	2 pairs per 15m ³	AS1012.1, AS1012.8, AS1012.9
Concrete Placement	Finished Levels	15m ³	1 cross section per 15m	Survey and 3m Straight Edge
Backfilling	Material Quality			
	- Maximum particle size	1 contract/ material type	1 per 200m ³ or lot	
	- Plasticity Index	1 contract/ material type	1 per 200m ³ or lot	AS1289.3.3.1
	Compaction	1 day's work or max 200m ²	1 per 200m ² or lot	AS1289.5.4.1
Sprayed Concrete	Test Panels and Cores	1 contract	3 test panels and 4 cores per mix design	AS1012.4, AS1012.9 AS1012.14
	Compressive Strength Cores	15m ³	2 per 15m ³	AS1012.4, AS1012.9 AS1012.14
	Curing Material Quality - Supplier's documentary evidence and certification	1 contract	1 per production batch	

* Note: or part thereof, per lot

Sub-Annexure B14

PAVEMENT MARKINGS (Specification C261)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Materials Supply	Material Quality - Supplier's documentary evidence and certification of:			
	- Paint	1 contract	1 per contract or change in material	
	- Glass Beads	1 contract	"	
	- Thermoplastic Material	1 contract	"	
	- Raised Pavement Markers	1 contract	"	
Paint Application	Wet Film Thickness	1 contract	1 per site visit or change in pressure settings	AS 1580.107.3
	Application Rate of Glass Beads	1 contract	1 per site visit or change in pressure settings	Annexure C261A
Thermoplastic Application	Cold Film Thickness	1 contract	1 per site visit or change in pressure settings	Measure by micrometer
	Application Rate of Glass Beads	1 contract	1 per site visit or change in pressure settings	Annexure C261A

Sub-Annexure B15
SIGNPOSTING (Specification C262)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Materials Supply	Material Quality - Supplier's documentary evidence and certification of:			
	- Sign Blanks	1 contract	1 per contract, or change in material	
	- Aluminium Extrusion Backing	1 contract	"	
	- Retro-reflective Material	1 contract	"	
	- Non-reflective Paint	1 contract	"	
	- Non-reflective Sheet Material	1 contract	"	
	- Steel Sign Support Structures	1 contract	"	
Concrete Foundations	Refer 'Minor Concrete Works'			

Sub-Annexure B16
LANDSCAPING (Specification C273)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Seed	Certification of Authenticity for the prescribed Mix	1 contract	Certification for each production batch delivered	
Imported Topsoil	Material Quality - pH - Organic Content - Soluble Salt Content	10,000m ² 10,000m ² 10,000m ²	1 per 500m ³ 1 per 500m ³ 1 per 500m ³	AS4419
Mulch for Planting	Material Quality	1 contract	1 contract	AS4454

Sub-Annexure B17
WATER RETICULATION (Specification C401)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Materials Supply	Material Quality - Supplier's documentary evidence and certification of: - uPVC Pipes - Ductile Iron Pipes - Copper Pipe - Polyethylene Pipe - Stop Valves Material - Non Return Valves - Spring Hydrants	1 contract 1 contract 1 contract 1 contract 1 contract 1 contract 1 contract	1 per contract " " " " " 1 per contract	AS2977 AS2280 and AS2129 AS1432 AS1159 AS2638 and AS2129 AS3578 AS2544 or AS3952
Siting and Excavation	Geometry	1 line	1 per line	Survey
Bedding/Embedment Material	Material Quality - Grading - Plasticity Index	1 contract	1 per contract per source	AS2032 AS1289.3.3.1
Thrust and Anchor Blocks	Refer Annexure C13			
Concrete Encasement	Refer Annexure C13			
Chamber Covers and Frames	Geometry	1 cover/frame	1 per cover/frame	survey
Testing of Pipelines	Pressure testing	1 line	1 per line	As specified C401.28
Backfill and Compaction	Compaction	1 line	1 per 2 layers max 100m ² (Full 300mm test depth)	AS1289.5.7.1 or AS1289.5.4.1
Switchgear and Controlgear Assembly	Electrical function	each installation	1 factory test per installation	AS3439
Commissioning of Pumping Station	Certification testing of electrical installation in accordance with relevant Australian Standards	1 installation	1 per installation	

Sub-Annexure B18
SEWERAGE SYSTEM (Specification C402)

ACTIVITY	KEY QUALITY VERIFICATION REQUIREMENTS	MAXIMUM LOT SIZE	MINIMUM TEST FREQUENCY	TEST METHOD
Materials Supply	Material Quality - Supplier's documentary evidence and certification of: - uPVC Pipes - Ductile Iron Pipes - Vitrified Clay Pipes - Precast Access Chambers	1 contract 1 contract 1 contract 1 contract	1 per contract " " "	AS1477 AS2280 and AS2129 AS1741 AS4198
Siting and Excavation	Geometry	1 line/structure	1 per line/structure	Survey
Bedding/Embedment Material	Material Quality - Grading - Plasticity Index	1 contract	1 per contract per source	AS1152 AS1289.3.3.1
Concrete Bedding	Refer Annexure C13			
Laying and Jointing of Pipes, Access Chambers, Structures	Geometry	1 line	1 per line	Survey
Thrust and Anchor Blocks	Refer Annexure C13			
Concrete Encasement	Refer Annexure C13			
Cast-in-situ Access Chambers	Material Quality - Tri-Calcium Aluminate Content - Fineness Index - Minimum Cement Content	1 contract 1 contract 1 contract	1 per contract per source " "	AS3972 AS3972 AS3972
Acceptance Test of Gravitation Mains, Access Chambers and Rising Mains	- Compressed Air Testing - Hydrostatic Testing	1 line 1 per test length Test length = $\frac{1370}{\text{pipeline dia. (mm)}}$	1 per line 1 per line	As specified C402.36 C402.37 C402.40 As specified C402.38 C402.40
Backfill and Compaction	Compaction	1 line	1 per 2 layers max 100m ² (Full 300mm test depth)	AS1289.5.7.1 or AS1289.5.4.1
Switchgear and Controlgear Assembly	Electrical Compliance	each installation	1 factory test per installation	AS3439
Commissioning of Pumping Station	Certification testing of electrical installation in accordance with relevant Australian Standards	1 installation	1 per installation	

